

Section 01 EOP Information	Site: ATL01A	Procedure Type: EOP	System: Safety	Equipment System: Inclement Weather				
Required Parts, Tools and Materials	Stack Inclement Weather AP Fuel measuring Stick. BMS/EPMS access			Severity 4				
EOP Overview:	This procedure outlines the steps to be performed when there is inclement weather. This can be used for high winds, flash flooding, snow, hurricane, thunderstorm, etc.							
Section 02 Risk & Safety Requirements	Risk and Safety Requirements							
1. Risks: 1.1 It is impossible to plan for every emergency scenario and the operators need to ensure the proper EOP is being used for the event. 1.2 Human intervention is not always preferred and could cause the event to have larger impact than allowing the critical facility to operate as intended. This should be considered during all events. 1.3 The potential risk of not following this procedure is an adverse effect on client load, or personnel injury. 2. Safety Requirements: 2.1 Proper PPE must be worn, and specific items will be listed in the detailed procedure where applicable. 2.2 In the event of injury, contact 911								
Section 03 Detailed Procedure	Detailed Procedures							
Action			Time	Initials				
1. Record date and time of event			Date: 1/10/25 0000	DR				
2. Site Operations to open a SEV4 bridge via PagerDuty to alert the COM of the potential for inclement weather and possible disruption of utility power.			1110	DR				
3. Create an emergency work order in NetSuite to track the event and to record all items being completed in preparation for inclement weather.			1115	DR				
Communication								
4. Monitor weather forecast to assess potential impact.			1118	DR				
5. Communicate with shift personnel about the potential impact of the storm.			1118	DR				
6. Outline a response plan in the event of an emergency. Possible Winter Storm with accumulating Snow and Ice. <i>Under Winter Storm Watch From 1/10/25 7AM 1/11/25</i>			1118	DR				
7. Contact fuel supplier(s) to ensure standby status. <i>7AM</i>				DR				
Administration								
8. Ensure emergency contact/escalation information is up to date.			1120	DR				
Facility Inspection & Preparation								
9. Measure all six (6) generator fuel levels (in inches):								
Gen 1	Gen 2	Gen R	Gen 3	Gen 4	Gen 5	Gen LS		
16	16	14	16	17	19	16		
Caution: if any generator is below 22" (75%), or 26" (75%) for Life Safety Generator contact fuel supplier for refueling.							1125	DR
10. Ensure all generator enclosure doors are properly secured.			1127	DR				

11. Ensure sump pump is functional and available to evacuate onsite fiber vaults if applicable.	1200	DA
12. Inspect the exterior of the building for debris/unsecured equipment.	1220	DA
13. If necessary, anchor any loose equipment that cannot be brought indoors.	1225	DA
14. Inspect and remove any obstructions from outside storm drains.	1225	DA
15. Inspect doors/windows for possibilities of water intrusion.	1225	DA
16. If necessary, protect door/window glass by affixing with adequate material.	N/A	DA
17. If necessary, use sandbags in front of doors to prevent water intrusion.	N/A	DA
18. Inspect fire riser system is operating per design.	1235	DA
19. Inspect designated first aid kits for adequate supplies.	1245	DA
20. Inspect designated AEDs for proper operation.	1245	DA
21. If necessary, remove all spill kits from mechanical yard 500.	1309	DA

Supply Inventory

22. Ensure adequate supply of cots/air mattresses & clean blankets.	1145	DA
23. Ensure adequate supply of clean towels.		DA
24. Ensure adequate supply of food & drinking water available (dependent on severity).		DA
25. Ensure rubber boots & hip waders are available.		DA
26. Ensure wet-vacs, mops, & squeegees are available.		DA

Inclement Weather Event Checklist

27. Continue to monitor weather forecast and storm track for updates. 1/10/25 0700 to 1/11/25 0700	0700	DA
28. Increase frequency of tours every 2 hours minimum.		DA
29. Frequently communicate with security on the status of the exterior of the facility.		DA
30. Ensure emergency operating procedures are on station and have been thoroughly reviewed.		DA
31. Inspect doors/windows/overhead for evidence of water intrusion into the facility.		DA
32. Maintain adequate stock of food & drinking water.		DA
33. If any injury occurs due to the inclement weather immediately contact 911.		DA
34. Provide facility status and supplies update to ACOM/COM (at a pre-determined interval).		DA
35. Send out email notification to clients to communicate the potential of an inclement weather event.		DA
36. Ensure each step has been initialed and time stamped.		DA

Personnel who initial for performance of any step in this procedure are to provide their printed name and sample initial. If insufficient space is provided here, enter name and initial in the Comments Section.

Controller Printed Name

Initials

Dave Robertson

Operator Printed Name

Initials

Section 04

Back-out Procedures

Back-out Procedures

Action	Time	Initials
1. Back-out procedures will commence immediately if any problem/failure occurs that affects the critical		

2. Stop all work.		
3. If the nature of the problem includes flooding, fire, or threat to personnel safety, take immediate actions to correct.		
4. EOP supervisor has informed CFM immediately with details of problem/failure, actions taken, and		
5. Safely clear all tools and personnel from the work area.		
6. Corrective actions will be taken to restore the equipment and/or critical load with coordination		
7. After all systems are recovered, an evaluation on site will be made to determine if the work will recommence or be rescheduled for a later date.		
8. Work will recommence only with the permission of site management.		

Section 05 EOP Information	Review By Date: 1/8/2025	Equipment CMMS ID:	Work Order:
-------------------------------	-----------------------------	--------------------	-------------

Section 06 EOP Supporting Documentation	Supporting Documentation	
--	---------------------------------	--

1. Critical Facility Work Rules
2. STACK Disaster Recovery Plan

Section 08 EOP Approval	EOP Approvals	
----------------------------	----------------------	--

Peer Review:	Reviewers Name: Dave Robertson	Reviewers Title: COT	Date: 1/8/2025
Management Approval	Approvers Name: Jack Gillian	Approvers Title: COM	Date: 1/8/2025

Section 09 EOP Completion	Sign-off/Completion	
------------------------------	----------------------------	--

EOP Quality Assurance Completion:	EOP Quality Assurance Name:	EOP Quality Assurance Title:	Date:
-----------------------------------	-----------------------------	------------------------------	-------

Section 10 EOP Comments	Completion Comments	
----------------------------	----------------------------	--